LINCOLN COUNTY
SEPTIC SYSTEM PERMIT NO. DRAINFIELD REPLACEMENT

ISSUED TO: LARRY BRAUNBECK DATE: 9-13-83

ADDRESS: [redacted] Troy PHONE: [redacted]

ISSUED BY (sign.) John W Peterson, R.S.

INSPECTION BY (sign.) _____ DATE: _____

(You must notify the Department of Environmental Health a minimum of 8 working day hours before backfilling the septic system, so that it can be inspected.)

CONTRACTOR: M. Warrington

DESCRIPTION OF SYSTEM:

LOCATION OF PROPOSED SYSTEM Block 1 Lot 65 Angel Island

SEPTIC TANK Existing ~~1000~~ 750 gal. ABSORPTION AREA: approx 85 ft² drywell

SEWAGE DISCHARGE - gal/day No. OF BEDROOMS 2

WATER SUPPLY SOURCE Community SOIL Sandy Gravel SLOPE 2%

INSTRUCTIONS: Construct a drywell as per lot layout & septic system regs. Surround drywell w/ 1-2' of washed rock.

SKETCH OF LOT LAYOUT:

