NEW

LINCOLN COUNTY SEPTIC SYSTEM PERMIT

ISSUED TO: DEAN BYRNS PHONE: [redacted]

ADDRESS: [redacted] CONTRACTOR: SELF

ISSUED BY (sign.): Ronald K. Anderson R.S. DATE: 8-9-91

INSPECTION BY (sign.): _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act". Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of 8 working hours before backfilling the septic system, so that it can be inspected.

LOCATION OF PROPOSED SYSTEM: ANGEL ISLAND LOT 11 BLOCK 1


SEPTIC TANK: 1000 gal. ABSORPTION AREA: 300 ft^2 (minimum)

SEWAGE DISCHARGE: — gal/day No. OF BEDROOMS: 2


WATER SUPPLY SOURCE: ANGEL ISLAND PUBLIC SYSTEM SOIL: SANDY SILT LOAM SLOPE: 2-3%

INSTRUCTIONS: DIG A DITCH AT LEAST 150' IN LENGTH x 2½-3' DEEP x 2' WIDE ACCORDING TO LOT LAYOUT AND DITCH DIAGRAM. THIS SYSTEM WILL UTILIZE A LIFT STATION.

SKETCH OF LOT LAYOUT: - NO SCALE -



- NOTE - DRAINFIELD LAYOUT SHOWN IS ONLY REPRESENTATIVE; YOU CAN LAY THE DITCHES THROUGH THE TREES, AS NEEDED.



DITCH DIAGRAM