LINCOLN COUNTY SEPTIC SYSTEM PERMIT

ISSUED TO: John A. Cooper [redacted] PHONE: [redacted]

ADDRESS: [redacted] CONTRACTOR: John Kampfe

ISSUED BY: John Peterson, RS DATE: 8/26/92

INSPECTION BY: _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-Site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act". Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of eight (8) working hours before backfilling the septic system, so that it can be inspected.

LOCATION OF PROPOSED SYSTEM: Angel Island BL 2 L 20

SEPTIC TANK: 1000 gal. ABSORPTION AREA: 300 ft²

SEWAGE DISCHARGE: ~ gal/day NUMBER OF BEDROOMS: 2 - Camper

WATER SUPPLY SOURCE: Community Well SOIL: Sandy, Gravelly SLOPE: 0%

INSTRUCTIONS: Drainfield Dig a ditch 150' long x 2½-3' deep x 2' wide according to lot layout & septic system regulation. Slope of pipe should not exceed a 1% drop. 1½'

SKETCH OF LOT LAYOUT:

