LINCOLN COUNTY SEPTIC SYSTEM PERMIT

This permit replaces one issued 4/5/90.

ISSUED TO: FRANK D. CROSS PHONE: [redacted]

ADDRESS: General Delivery Troy CONTRACTOR: Kootenai Valley Const.

ISSUED BY (sign.): John D Peterson, RS DATE: 7-8-91

INSPECTION BY (sign.): _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act". Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of 8 working hours before backfilling the septic system, so that it can be inspected.

LOCATION OF PROPOSED SYSTEM: KOOTENAI RIVER ESTATES LOT 2

SEPTIC TANK: 1000 gal. ABSORPTION AREA: 260 ft²

SEWAGE DISCHARGE: ~ gal/day NO. OF BEDROOMS: 2

WATER SUPPLY SOURCE: Well SOIL: Clay SLOPE: 0%

DRAINFIELD INSTRUCTIONS: Dig a ditch 130' long x 2½-3' deep x 2' wide according to lot layout & septic system regulation. Slope of pipe should not exceed a 1% drop.

SKETCH OF LOT LAYOUT:

