LINCOLN COUNTY
SEPTIC SYSTEM PERMIT NO. Repl.

ISSUED TO: OWEN ERICKSON DATE: 5-8-85

ADDRESS: [redacted] PHONE: [redacted]

ISSUED BY (sign.) John Peterson, R.S.

INSPECTION BY (sign.) _____ DATE: _____

(You must notify the Department of Environmental Health a minimum of 8 working day hours before backfilling the septic system, so that it can be inspected.)

CONTRACTOR: _____

DESCRIPTION OF SYSTEM:

LOCATION OF PROPOSED SYSTEM Angel Island Block 1 Lot 79

SEPTIC TANK Existing 750 gal. ABSORPTION AREA: 2-ring drywell

SEWAGE DISCHARGE — gal/day No. OF BEDROOMS 1

WATER SUPPLY SOURCE Community SOIL Silt SLOPE 3-4%

INSTRUCTIONS: Construct a 2-ring drywell as an overflow for existing seepage bed. Surround drywell rings w/ at least 2' of washed rock. Keep drywell at least 10' from water line

SKETCH OF LOT LAYOUT:

