LINCOLN COUNTY
SEPTIC SYSTEM PERMIT NO. DRAINFIELD REPLACEMENT

ISSUED TO: HALFWAY HOUSE C/o Merlin Spiering DATE: 9-9-83

ADDRESS: [redacted] Troy PHONE: [redacted]

ISSUED BY (sign.) John Peterson R.S.

INSPECTION BY (sign.) _____ DATE: _____

(You must notify the Department of Environmental Health a minimum of 8 working day hours before backfilling the septic system, so that it can be inspected.)

CONTRACTOR: Self

DESCRIPTION OF SYSTEM:

LOCATION OF PROPOSED SYSTEM Halfway House on Bull Lake

SEPTIC TANK existing - gal. ABSORPTION AREA: approx 200 ft²

SEWAGE DISCHARGE - gal/day No. OF BEDROOMS -

WATER SUPPLY SOURCE Payne Creek SOIL Silty loam SLOPE 0-2%

INSTRUCTIONS: DRAINFIELD Dig a ditch approx 100' long x 2½-3' deep x 2' wide according to site layout and septic system regs. Slope of pipe should not exceed a 1% drop.

SKETCH OF LOT LAYOUT:

