file

LINCOLN COUNTY SEPTIC SYSTEM PERMIT

ISSUED TO: Scott Lapka PHONE: [redacted]

ADDRESS: [redacted] CONTRACTOR: M. Orr

ISSUED BY (sign.): John W Peterson, RS DATE: 8-16-91

INSPECTION BY (sign.): _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act". Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of 8 working hours before backfilling the septic system, so that it can be inspected.

LOCATION OF PROPOSED SYSTEM: Bull Lake Peak Tracts lot 6

Proposed
SEPTIC TANK: 1000 gal. ABSORPTION AREA: 15×30 seepage bed ft²

SEWAGE DISCHARGE: ~ gal/day No. OF BEDROOMS: 1-2

Proposed
WATER SUPPLY SOURCE: well SOIL: gravelly Sandy Silt SLOPE: 1-4%

INSTRUCTIONS: Construct a seepage bed on per lot lay out and septic system regulation. Permit is void after proof that no groundwater is w/in 7' of the ground surface in seepage bed area. SKETCH OF LOT LAYOUT:

