ISSUED TO: DAVID McDONALD PHONE: [redacted]

ADDRESS: [redacted] CONTRACTOR:

ISSUED BY (sign.): Johnnie Peterson, RS DATE: 5-4-92

INSPECTION BY (sign.): DATE:

*PLEASE NOTE: The Lincoln County "On-site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act". Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of 8 working hours before backfilling the septic system, so that it can be inspected.

LOCATION OF PROPOSED SYSTEM: Lot 17 Gordon Beach Bull Lk.

SEPTIC TANK: 1000 gal. ABSORPTION AREA: 400 ft²

SEWAGE DISCHARGE: ~ gal/day No. OF BEDROOMS: 3

WATER SUPPLY SOURCE: Well SOIL: Gravelly, Sand SLOPE: 0 %

INSTRUCTIONS: Dig a ditch 200' long x 2½-3' deep x 2' wide according to Lot layout & Septic System regulation. Slope of pipe should not exceed a 1% drop.

