LINCOLN COUNTY SEPTIC SYSTEM PERMIT

ISSUED TO: Donald Riddle PHONE: [redacted]

ADDRESS: [redacted] CONTRACTOR: Self

ISSUED BY (sign.): John W Peterson, RS DATE: 8-18-89

INSPECTION BY (sign.): _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act". Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of 8 working hrs. before backfilling the septic system, so that it can be inspected.

LOCATION OF PROPOSED SYSTEM: Lot 11, Block 9 Angel Island

SEPTIC TANK: Concrete 1000 gal. ABSORPTION AREA: 450 ft²

SEWAGE DISCHARGE: ~ gal/day No. OF BEDROOMS: 1- trailer

WATER SUPPLY SOURCE: Community SOIL: Clay-loam SLOPE: 0-1%

INSTRUCTIONS: Construct a seepage bed as per lot layout & septic system regulation. Slope of pipe in bed should be a 0% grade.

SKETCH OF LOT LAYOUT:

