file

LINCOLN COUNTY SEPTIC SYSTEM PERMIT

ISSUED TO: KEN TORKELSON PHONE: [redacted]

ADDRESS: [redacted] CONTRACTOR: _____

ISSUED BY (sign.): John W Peterson, RS DATE: 6-12-92

INSPECTION BY (sign.): _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act". Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of 8 working hours before backfilling the septic system, so that it can be inspected.

LOCATION OF PROPOSED SYSTEM: Angel Island Block 3 Lot 40 M.N.

SEPTIC TANK: 750 gal. ABSORPTION AREA: 240 ft²

SEWAGE DISCHARGE: ~ gal/day No. OF BEDROOMS: 1-2

WATER SUPPLY SOURCE: Community SOIL: Silty Loam SLOPE: 0-10%

INSTRUCTIONS: Drainfield Dig a ditch 120' long x 2½-3' deep x 2' wide according to Lot Layout & Septic System regulation. Slope of pipe should not exceed a 1% drop.

SKETCH OF LOT LAYOUT:

1=30'

