Replacement

LINCOLN COUNTY SEPTIC SYSTEM PERMIT

ISSUED TO: SALLY TOW PHONE: [redacted]

ADDRESS: [redacted] CONTRACTOR: Dennis Walton

ISSUED BY (sign.): John Peterson, RS DATE: 9-26-88

INSPECTION BY (sign.) _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act" Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of 8 working hrs. before backfilling the septic system, so that it can be inspected.

LOCATION OF PROPOSED SYSTEM: Angel Island Block 2 Lot 6

Existing
SEPTIC TANK: 1000 gal. ABSORPTION AREA: 4'x8' Seepage Pit ft²

SEWAGE DISCHARGE: ~ gal/day No. OF BEDROOMS: 4

WATER SUPPLY SOURCE: Community SOIL: Silt-clay SLOPE: 0%

INSTRUCTIONS: Construct a overflow drain pit at least 4' wide x 8' long x 8' deep according to lot layout, and fill pit with washed rock. Connect ends of existing drainfield together and run pipe into the pit

SKETCH OF LOT LAYOUT:

