Replacement

LINCOLN COUNTY SEPTIC SYSTEM PERMIT

ISSUED TO: VERN WHITE PHONE: _____

ADDRESS: [redacted] CONTRACTOR: F. McDougall

ISSUED BY (sign.): John D Peterson, RS DATE: 11-15-91

INSPECTION BY (sign.): _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act". Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of 8 working hours before backfilling the septic system, so that it can be inspected.

LOCATION OF PROPOSED SYSTEM: Block 9 Lot 16 Angel Island

Existing
SEPTIC TANK: _____ gal. ABSORPTION AREA: 2 ring drywell ft²

SEWAGE DISCHARGE: ~ gal/day No. OF BEDROOMS: 2

WATER SUPPLY SOURCE: Community SOIL: Silty Clay SLOPE: 0%

INSTRUCTIONS: Construct a drywell as per lot layout & septic system regulation. Surround rings w/at least 2' of washed rock.

SKETCH OF LOT LAYOUT:

