LINCOLN COUNTY HEALTH DEPARTMENT Permit #24-54998
ENVIRONMENTAL HEALTH
WASTEWATER TREATMENT AND DISPOSAL SYSTEM PERMIT

Issue Date: 11/25/2024 Expiration Date: 11/24/2025

Property Owner: Enos Miller

Mailing Address: [redacted]

Installer: Donavan Truman License #: 109

Approved Work: (Check One) ☒ New Installation ☐ Existing System

☐ Replace Drainfield ☐ Replace Tank ☐ Extension

Describe: Installation of new pressure dosed system for 3 Bedroom House.

Legal: S27, T37 N, R28 W, COS 3971, PARCEL B IN NESE, ACRES 6

Property Address: 335 W. Dodge Creek Rd., Rexford, MT 59930 Assessment Code: 54998

DEQ COSA: E.Q.#09-1413 Date: 01/08/2009

Approved Design Criteria: Installation of new pressure dosed system for 3 Bedroom House with 2 Laterals @ 125'. Septic tank size must be verified as 1000 gallon. Drainfield location in position #10(See Layout).

# of Bedrooms: 3 Septic Tank Size: 1000/500 gallons Trench Width:36"

# of Laterals: 2 Length of Laterals: 125' Trench Depth: 24"-36"

SYSTEM MUST INCLUDE INSTALLATION OF EFFLUENT FILTER AT SEPTIC TANK OUTLET!!

Special Instructions: Install system according to the COSA, lot layout, the Lincoln County Wastewater Treatment and Disposal Regulation, and Circular DEQ-4. It is the installer's responsibility to ensure that all required horizontal setbacks are met. CHANGES MUST BE PRE-AUTHORIZED BY THE DEPARTMENT.

Issued By: *Robin Blumberg, RS*

NOTICE: The Department must be notified at least 3 business days (72 hours) prior to backfilling the system. Call 406-283-2442. Any system not inspected by the Department or its designated representative prior to closure is an illegal installation in violation of Lincoln County Health Board Regulation Ch. 3. Illegal installations may result in fines and/or requirements to remove or reconstruct the system.

Closure Statement:

This system is in compliance with the approved design criteria and Lincoln County's Wastewater Treatment and Disposal Regulation.

Signed: Robin Blmby *Date:* 12/2/24

This permit is not finalized until the system is inspected and the closure statement is signed.

This permit is not a guarantee that the system will function properly for a prescribed period of time.

PLANS AND SPECIFICATIONS FOR DRAINFIELD(S) INSTALLATION

1) All drainfield (primary and replacement) laterals shall be durably staked and labeled. Elevations of each lateral shall be determined by use of a surveyor's level.

2) All drainfields shall be installed in the south drainfield area initially (primary site). The replacement for each drainfield will be north (northern drainfield area). The forcemain for the replacement area shall continue north between the existing (failed) laterals to the replacement area.

3) All drainfields shall be installed as each is permitted in the eastern end of the southern drainfield area. As each drainfield is permitted, the system shall be installed in the next closest staked site west the existing system. Therefore, all systems shall be installed in an east to west direction.

4) Existing systems must be durably staked and labeled upon backfilling.

5) No existing drainfield may be parked or driven over during installation (or any time) of new systems to prevent damage.

6) Each forcemain shall be permanently labeled and curb stopped at the SE end of southern drainfield area.

Reviewed by the Local Reviewing Authority
Under contract with the
Department of Environmental Quality/ PDO
Local Reviewer — Date 1/8/2009

Accepted under contract
DEQ Representative Barbara Kingery — Date 1/20/09
EQ# 09-1412

RECEIVED
JAN [illegible]
MEDFORD WATER
& SUBDIVISION BUREAU

DRAINFIELD(S) / FORCEMAIN(S) LAYOUT

