ISSUED TO: TED & MICHELLE CARPENTER PHONE: [redacted]

ADDRESS: [redacted] CONTRACTOR: TLC

ISSUED BY (sign.): John W Peterson, RS DATE: 6-5-92

INSPECTION BY (sign): _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act". Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of 8 working hours before backfilling the septic system, so that it can be inspected.

Marvel Occ Soils Parcel B 10 AC

LOCATION OF PROPOSED SYSTEM: SE¼ SW¼ SW¼ Sec 33 T37N R27W

Proposed
SEPTIC TANK: 1,000 gal. ABSORPTION AREA: 360 ft²

SEWAGE DISCHARGE: ~ gal/day No. OF BEDROOMS: 2

WATER SUPPLY SOURCE: Well SOIL: gravelly loam SLOPE: 5%

Drainfield
INSTRUCTIONS: Dig a ditch 180' long x 2½-3' deep x 2' wide according to lot layout and Septic System regulation. Slope of pipe should not exceed a 1' drop

SKETCH OF LOT LAYOUT:

