LINCOLN COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH
WASTEWATER TREATMENT AND DISPOSAL SYSTEM PERMIT

Issue Date: 09/29/2023 Expiration Date: 09/28/2024

Property Owner: John Catron

Mailing Address: [redacted]

Telephone: [redacted] E-mail: [redacted]

Installer: Caden Lamb License #: 193

Approved Work: (Check One) ☐ New Installation ☒ Existing System

☐ Replace Drainfield ☐ Replace Tank ☒ Extension

Describe: Two 65' laterals existing (sized for 2 bedroom). Add one additional 65' lateral.

Parcel Description:

Legal: Gateway Village Unit 9, S03 T37N R27W, Lot 35

Property Address: 236 Castle View Lane, Eureka Assessment Code: 10764

DEQ COSA: EQ#96-1351 Date: 12/27/95

Approved Design Criteria: Add one additional lateral to expand system for existing 3 bedroom house.

# of Bedrooms: 3 Septic Tank Size: 1000 Trench Width: 24"

# of Laterals: 3 (add 1, 2 exist) Length of Laterals: 65' Trench Depth: 24"-36"

SYSTEM MUST INCLUDE INSTALLATION OF EFFLUENT FILTER AT SEPTIC TANK OUTLET!!

Special Instructions: Install system according to the COSA, lot layout, the Lincoln County Wastewater Treatment and Disposal Regulation, and Circular DEQ-4. It is the installer's responsibility to ensure that all required horizontal setbacks are met. CHANGES MUST BE PRE-AUTHORIZED BY THE DEPARTMENT.

Issued By: *Kathi Hooper, RS*

NOTICE: The Department must be notified at least 3 business days (72 hours) prior to backfilling the system. Call 406-283-2442. Any system not inspected by the Department or its designated representative prior to closure is an illegal installation in violation of Lincoln County Health Board Regulation Ch. 3. Illegal installations may result in fines and/or requirements to remove or reconstruct the system.

Closure Statement:

This system is in compliance with the approved design criteria and Lincoln County's Wastewater Treatment and Disposal Regulation.

Signed: _____ *Date:* 10/23/23

✓ Lincoln County Health Department (LCHD) ____ Licensed Installer w/ approval of LCHD

DISCLAIMER

This permit is not a guarantee by the Department that the system will function properly for a prescribed period of time.

SV

Existing plan from
approval
Add 65' lateral to
existing drainfield. Provide
as built showing location.