file Copy

LINCOLN COUNTY SEPTIC SYSTEM PERMIT

ISSUED TO: William G. F. Cronkhite PHONE: [redacted]

ADDRESS: [redacted] CONTRACTOR: Koocanusa Pg

ISSUED BY (sign.): John W. Peterson, RS DATE: 10-10-90

INSPECTION BY (sign.): _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act" Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of 8 working hours before backfilling the septic system, so that it can be inspected.

Pluid ('89

LOCATION OF PROPOSED SYSTEM: SW¼ Sec 12 T36 R28 20 Ac. Remainder

MIN. SEPTIC TANK: 750 gal. ABSORPTION AREA: 300 ft² 250ft²/bdr

SEWAGE DISCHARGE: ~ gal/day No. OF BEDROOMS: 2

WATER SUPPLY SOURCE: Well SOIL: Silty loam SLOPE: 15 %

Drainfield INSTRUCTIONS: Dig a ditch 250' long x 2½-3' deep x 2' wide according to Lot Layout & Septic System regulation. Slope of pipe should not exceed a 1% drop.

REPRESENTATIVE SKETCH OF LOT LAYOUT:

