LINCOLN COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH
WASTEWATER TREATMENT AND DISPOSAL SYSTEM PERMIT

Issue Date: 05/18/2023 Expiration Date: 05/17/2024

Property Owner: Bruce Sickler

Mailing Address: [redacted]

Telephone: [redacted] E-mail:

Installer: Tony Berget License #: 26

Approved Work: (Check One) ☒ New Installation ☐ Existing System

☐ Replace Drainfield ☐ Replace Tank ☐ Extension

Describe: Installation of new system with chambers and 18" trenches.

Parcel Description:

Legal: PARKSIDE@FISHER RIVER, S14, T27 N, R28 W, LOT 6, ACRES 4.703, PM 6892

Property Address: 303 Roger's Mountain Loop Libby, MT 59923 Assessment Code: 56134

DEQ COSA: E.Q.#08-1226 Date: 04/18/2008

Approved Design Criteria: New gravity system with chambers and 18" trenches.

# of Bedrooms: 2 Septic Tank Size: 1000 gallons Trench Width: 24"

# of Laterals: 2 Length of Laterals: 76' Trench Depth: 18"

SYSTEM MUST INCLUDE INSTALLATION OF EFFLUENT FILTER AT SEPTIC TANK OUTLET!!

Special Instructions: Install system according to the COSA, lot layout, the Lincoln County Wastewater Treatment and Disposal Regulation, and Circular DEQ-4. It is the installer's responsibility to ensure that all required horizontal setbacks are met. Reduction given for chambers. CHANGES MUST BE PRE-AUTHORIZED BY THE DEPARTMENT.

Issued By: Robin Blumberg, S17

NOTICE: The Department must be notified at least 3 business days (72 hours) prior to backfilling the system. Call 406-283-2442. Any system not inspected by the Department or its designated representative prior to closure is an illegal installation in violation of Lincoln County Health Board Regulation Ch. 3. Illegal installations may result in fines and/or requirements to remove or reconstruct the system.

Closure Statement:

This system is in compliance with the approved design criteria and Lincoln County's Wastewater Treatment and Disposal Regulation.

Signed: Robin Blumberg *Date:* 9/26/23

_____ Lincoln County Health Department (LCHD) _____ Licensed Installer w/ approval of LCHD

This permit is not finalized until the system is inspected and the closure statement is signed.

This permit is not a guarantee that the system will function properly for a prescribed period of time.

Loop
Rogers Mt.
Ridge line
Infiltrators
76'
D-Box
76'
240'
Tank
150'
165'
Well
30'
28'