LINCOLN COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH
WASTEWATER TREATMENT AND DISPOSAL SYSTEM PERMIT

Issue Date: 10/31/2022 Expiration Date: 10/30/2023

Property Owner: Mark & Sheila Eustice

Mailing Address: [redacted]

Telephone: [redacted] Email:

Installer: Charley Follensbee License #: 96

Approved Work: (Check One) ☐ New Installation ☒ Existing System

☒ Replace Drainfield ☐ Replace Tank ☐ Extension

Describe: Gravity system with standard trenches, chambers

Parcel Description:

Legal: Fort Eustice/Spruce View, Lot 2, S9 T36N R26W, 2.167 acres

Property Address: 3420 Sinclair Creek Rd. Assessment Code: 6867

Approved Design Criteria:

# of Bedrooms: 2 Septic Tank Size: 1000 gallons Trench Width: 24 inches

# of Laterals: 4 Length of Laterals: ~~100~~ 94 feet Trench Depth: 24-36 inches

SYSTEM MUST INCLUDE INSTALLATION OF EFFLUENT FILTER AT SEPTIC TANK OUTLET!!

Special Instructions: Install system according to the lot layout, the Lincoln County Wastewater Treatment and Disposal Regulation, and Circular DEQ-4. ANY CHANGES MUST BE PRE-AUTHORIZED BY THE DEPARTMENT.

Issued By: *Kathi J. Hooper, R.S.*

NOTICE: The Department must be notified at least 3 business days (72 hours) prior to backfilling the system. Call 406-283-2442. Any system not inspected by the Department or its designated representative prior to closure is an illegal installation in violation of Lincoln County Health Board Regulation Ch. 3. Illegal installations may result in fines and/or requirements to remove or reconstruct the system.

Closure Statement:

I, _____, have inspected this system and found it to be in compliance with the approved design criteria and Lincoln County's Wastewater Treatment and Disposal Regulation.

Signed: _____ *Date:* _____

_____ Lincoln County Health Department (LCHD) _____ Licensed Installer w/ approval of LCHD

DISCLAIMER

This permit is not a guarantee by the Department that the system will function properly for a prescribed period of time.

N
Sinclair Ck Rd
State Land
Lot1 1acre
Lot2 2.460 Acres
New well
37'
100'
Existing Well
65'x2
Existing 1000 G Tank
2 Bd Home
New Drainfield
55'
New Replacement
100'