Original permit - Bill Dennis 7-20-77

Replacement

LINCOLN COUNTY SEPTIC SYSTEM PERMIT

ISSUED TO: Russell Hartly PHONE: [redacted]

ADDRESS: [redacted] CONTRACTOR: Self

ISSUED BY (sign.): John Peterson, RS DATE: 4-11-89

INSPECTION BY (sign.): _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act" Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of 8 working hrs. before backfilling the septic system, so that it can be inspected.

LOCATION OF PROPOSED SYSTEM: Jensen's Addition Lot L Block B

SEPTIC TANK: existing 1000 gal. ABSORPTION AREA: 400 ft²

SEWAGE DISCHARGE: ~ gal/day No. OF BEDROOMS: 3

WATER SUPPLY SOURCE: City SOIL: Silt SLOPE: 0%

INSTRUCTIONS: Dig a ditch 200' long x 2½-3' deep x 2' wide according to lot layout & septic system regulations Drain pipe should not exceed a 1% drop

SKETCH OF LOT LAYOUT:

