LINCOLN COUNTY
SEPTIC SYSTEM PERMIT NO. New

ISSUED TO: Skip Bloomstine DATE: 5-26-87

ADDRESS: [redacted] PHONE:

ISSUED BY (sign.) John Peterson, RS

INSPECTION BY (sign) DATE:

(You must notify the Department of Environmental Health a minimum of 8 working day hours before backfilling the septic system, so that it can be inspected.)

CONTRACTOR: Kooceusa Plumbing

DESCRIPTION OF SYSTEM:

LOCATION OF PROPOSED SYSTEM SW¼ SW¼ NW¼ Sec 20 T37N R27W 9 Acr.

Proposed SEPTIC TANK 1000 gal. Proposed ABSORPTION AREA: 320 ft² 125 ft 2/bd

SEWAGE DISCHARGE — gal/day No. OF BEDROOMS 2

WATER SUPPLY SOURCE well SOIL Si. Lt. Sand SLOPE 1½ %

Drain field INSTRUCTIONS: Dig a ditch 160' long x 2½-3' deep x 2' Wide accordi to lot layout & septic system reg. Slope of pipe should not exceed a 1% drop.

SKETCH OF LOT LAYOUT:

