ISSUED TO: JAMES LIDSTER PHONE: % Jim Voyles [redacted]

ADDRESS: % Deep Creek Const. CONTRACTOR: Deep Creek Const. [redacted]

ISSUED BY: Johnnie Peterson, RS DATE: 8-31-92

INSPECTION BY: _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-Site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act". Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of eight (8) working hours before backfilling the septic system, so that it can be inspected.

LOCATION OF PROPOSED SYSTEM: Glen Lk Park Amended Block 1 Lot 1 NW¼ Sec 22 T36 R26

SEPTIC TANK: 1000 gal. ABSORPTION AREA: 260 ft²

SEWAGE DISCHARGE: ~ gal/day NUMBER OF BEDROOMS: 2

WATER SUPPLY SOURCE: Well SOIL: Sandy loam w/gravel SLOPE: 0%

INSTRUCTIONS: Drainfield Dig a ditch 130' long x ½ - 1' deep x 2' wide according to lot layout & Septic System regulation. Slope of pipe should not exceed a 1% drop. Place 12" of fine to Med. grade sand below drainfield rock in trench.

SKETCH OF LOT LAYOUT:

