LINCOLN COUNTY SEPTIC SYSTEM PERMIT

ISSUED TO: RONALD C MORGAN, SR PHONE: [redacted]

ADDRESS: [redacted] CONTRACTOR: Kootenusa Pi

ISSUED BY (sign.): Johnny Peterson, R.S. DATE: 4-28-89

INSPECTION BY (sign.) _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act" Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of 8 working hrs. before backfilling the septic system, so that it can be inspected.

LOCATION OF PROPOSED SYSTEM: Pine Valley Acres Lot 16 (W. Koot.)

SEPTIC TANK: 1,000 gal. ABSORPTION AREA: 300 ft²

SEWAGE DISCHARGE: - gal/day No. OF BEDROOMS: 1

WATER SUPPLY SOURCE: well SOIL: Gravelly loam SLOPE: 4/4 %

INSTRUCTIONS: Drain field Dig a ditch 150' long x 2½-3' deep x 2' wide according to Lot layout & septic System regulations. Slope of pipe should not exceed a 1% drop.

SKETCH OF LOT LAYOUT:

