LINCOLN COUNTY SEPTIC SYSTEM PERMIT

ISSUED TO: Richard Schrade PHONE: [redacted]

ADDRESS: [redacted] CONTRACTOR: Julius Robertson [redacted]

ISSUED BY (sign.): John Robertson, RS DATE: 3/11/88

INSPECTION BY (sign.): _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act". Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of 8 working [redacted] before backfilling the septic system, so that it can be inspected.

LOCATION OF PROPOSED SYSTEM: Adjacent to Heritage Museum (to East)

SEPTIC TANK: 750 gal. ABSORPTION AREA: 2-3' rings ft²

SEWAGE DISCHARGE: — gal/day No. OF BEDROOMS: — Shop toilet & lav.

WATER SUPPLY SOURCE: Well SOIL: Rocky loam SLOPE: 0%

INSTRUCTIONS: Construct a drywell as per lot layout & septic system req's. Surround rings w/ at least 3' of washed rock.

SKETCH OF LOT LAYOUT:

