LINCOLN COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH
WASTEWATER TREATMENT AND DISPOSAL SYSTEM PERMIT

Issue Date: 08/11/2025 (Renewal) 05/06/2024 Expiration Date: 08/10/2026 Permit#25-50471

Property Owner: Richard and Melissa Westbury

Mailing Address: [redacted]

Installer: Homeowner License #:

Approved Work: (Check One) ☒ New Installation ☐ Existing System

☐ Replace Drainfield ☐ Replace Tank ☐ Extension

Describe: Installation of new gravity system for 2 Bedroom House.

Parcel Description:

Legal: MBMI DEVELOPMENT INC., S25, T31 N, R31 W, ACRES 1.621, LOT 6 PM 7152

Property Address: 127 Margaret Ln., Libby, MT 59923 Assessment Code: 50471

DEQ COSA: EQ# 09-1880 Date: 04/24/2009

Approved Design Criteria: Installation of new gravity system with 2 Lateral @ 96' with reduction for chambers. Minimum 5' natural soil between trenches, maximum trench width 24", trench depth 24"-36".

# of Bedrooms: 2 Septic Tank Size: 1000 gallons Trench Width: 24"

# of Laterals: 2 Length of Laterals: 96' Trench Depth: 24-36"

SYSTEM MUST INCLUDE INSTALLATION OF EFFLUENT FILTER AT SEPTIC TANK OUTLET!!

Special Instructions: Install system according to the lot layout, the Lincoln County Wastewater Treatment and Disposal Regulation, Circular DEQ-4, and COSA(If Applies). It is the installer's responsibility to ensure that all required horizontal setbacks are met. CHANGES MUST BE PRE-AUTHORIZED BY THE DEPARTMENT.

Issued By: *Robin Blumberg, R.S.*

NOTICE: The Department must be notified at least 3 business days (72 hours) prior to backfilling the system. Call 406-283-2442. Any system not inspected by the Department or its designated representative prior to closure is an illegal installation in violation of Lincoln County Health Board Regulation Ch. 3. Illegal installations may result in fines and/or requirements to remove or reconstruct the system.

Closure Statement:

This system is in compliance with the approved design criteria and Lincoln County's Wastewater Treatment and Disposal Regulation.

Signed: _____ *Date:* _____

This permit is not finalized until the system is inspected and the closure statement is signed.

This permit is not a guarantee that the system will function properly for a prescribed period of time.

REVISED LOT LAYOUT
MBMI DEVELOPMENT INC. SUBDIVISION
GEOCODE 56-4283-25-4-01-23-0000
EQ # 09-1880
SECTIONS 25, 36
T.31N, R.31W
SE 1/4, SE 1/4 LOT #6
LINCOLN COUNTY
LIBBY, MONTANA

RICHARD + MELISSA WESTBURY 4/19/24

