LINCOLN COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH
WASTEWATER TREATMENT AND DISPOSAL SYSTEM PERMIT

Issue Date: 05/30/2025 (Renewal) 05/07/2024 Expiration Date: 05/29/2026 Permit# 25-50267

Property Owner: Krispin Lihme

Mailing Address: [redacted]

Installer: Krispin Lihme License #: 201

Approved Work: (Check One) ☒ New Installation ☐ Existing System

☐ Replace Drainfield ☐ Replace Tank ☐ Extension

Describe: Installation of new pressure dosed system for 3 Bedroom House.

Parcel Description:

Legal: S06, T35 N, R26 W, COS 4242, ACRES 5.87

Property Address: 593 Rocky Road, Eureka, MT 59917 Assessment Code: 50267

DEQ COSA: EQ#98-1852 Date: 12/10/1997

Approved Design Criteria: Installation of new pressure dosed system with 11 laterals(4@100', 4@40',33',32,'10')and squirt test must show no greater than 10% variation across entire system. Existing well to be abandoned and proposed well drilled in approved lot location.

# of Bedrooms: 3 Septic Tank Size: 2500/500 gallons Trench Width: 36"

# of Laterals: 11 Length of Laterals: See design. Trench Depth: 24-36"

SYSTEM MUST INCLUDE INSTALLATION OF EFFLUENT FILTER AT SEPTIC TANK OUTLET!!

Special Instructions: Install system according to the COSA, lot layout, the Lincoln County Wastewater Treatment and Disposal Regulation, and Circular DEQ-4. It is the installer's responsibility to ensure that all required horizontal setbacks are met. Reduction given for chambers. CHANGES MUST BE PRE-AUTHORIZED BY THE DEPARTMENT.

Issued By: Robin Blumberg, R.S.

NOTICE: The Department must be notified at least 3 business days (72 hours) prior to backfilling the system. Call 406-283-2442. Any system not inspected by the Department or its designated representative prior to closure is an illegal installation in violation of Lincoln County Health Board Regulation Ch. 3. Illegal installations may result in fines and/or requirements to remove or reconstruct the system.

Closure Statement:

This system is in compliance with the approved design criteria and Lincoln County's Wastewater Treatment and Disposal Regulation.

Signed: Robin Blumberg *Date:* 9/4/25

This permit is not finalized until the system is inspected and the closure statement is signed.

This permit is not a guarantee that the system will function properly for a prescribed period of time.

SV

543 Rocky Rd Eureka

Distribution Plan

Pressure Dose system

