LINCOLN COUNTY SEPTIC SYSTEM PERMIT

ISSUED TO: ROBERT McCLURE PHONE: [redacted]

ADDRESS: [redacted] CONTRACTOR: TIMBERLINE

ISSUED BY: John Peterson, RS DATE: 9-14-92

INSPECTION BY: _____ DATE: _____

*PLEASE NOTE: The Lincoln County "On-Site Sewage Disposal Regulation" does not conform with all requirements of the Montana State "Sanitation in Subdivision Act". Therefore, septic systems permitted under the county regulation may not be approvable for the purpose of future land division health reviews.

You must notify the Department of Environmental Health a minimum of eight (8) working hours before backfilling the septic system, so that it can be inspected.

LOCATION OF PROPOSED SYSTEM: NE¼ SE¼ Sec 9 T 36 R 26 Sinclair Cr.

SEPTIC TANK: 1000 gal. ABSORPTION AREA: 85 x 2 ft²

SEWAGE DISCHARGE: _____ gal/day NUMBER OF BEDROOMS: 2

WATER SUPPLY SOURCE: Spring SOIL: Rocky Loam SLOPE: _____

INSTRUCTIONS: Construct a drywell as per lot layout & Septic System regulation. Surround drywell rings w/ at least 2' of washed rock.

SKETCH OF LOT LAYOUT:

