LINCOLN COUNTY
DEPARTMENT OF ENVIRONMENTAL HEALTH
WASTEWATER TREATMENT AND DISPOSAL SYSTEM PERMIT

Issue Date: 7/18/2018 Expiration Date: 7/18/2019

Property Owner: Troy Investments, LLC c/o: Doug Watson

Address: [redacted]

Telephone: (Home) [redacted] (Work)

Installer: Dennis Redlinger License No. 23

__xx__ New Installation ____ Existing System

____ Repair ____ Replacement ____ Extension ____ Other

Describe: Three 80' laterals using drainrock and perf pipe.

Parcel Description:

Legal: S16 T34 R33

Address or Location: Burnt Creek Hideaway Lot 1

Geo/Assessors code: 0000050383

Approved Design Criteria:

Bedrooms 2 Septic Tank Size: 1000 gallons Drainfield Size: 240 Linear Feet

SYSTEM MUST INCLUDE INSTALLATION OF EFFLUENT FILTER AT SEPTIC TANK OUTLET !!

Special Instructions: INSTALL SYSTEM ACCORDING TO LAYOUT, DEQ-4 AND LINCOLN COUNTY WASTEWATER REGULATION #3. ANY DEVIATIONS FROM APPROVED PLAN MUST BE AUTHORIZED BY THE DEPARTMENT.

Issued By: Jake Mertes, R.S.

Closure Statement:

I, _____, have inspected this system and found it to be in compliance with the conditions of the permit, and the Lincoln County Wastewater Treatment and Disposal Regulation.

Signed: _____ *Date:* _____

Title: _____

NOTICE: The Department must be notified at least 48 hours prior to backfilling the system. Any system not inspected by the Department or its designated representative prior to closure is an illegal installation in violation of Lincoln County Health Board Regulation No. 3. Illegal installations may result in fines and/or requirements to remove or reconstruct the system.

406-283-2442

DISCLAIMER

This permit is not a guarantee by the Department that the system will function properly for a prescribed period of time.

Notes and References:

Scale: 1" = 455'

Lot 1, Burnt Creek Hideaway Subdivision.

Sketches of structures not to scale.

Lookout-design house will be off electrical grid.

1. Proposed site of solar panel tower;

   Lookout design housing is off grid.

2. Proposed well site.

3. Proposed septic tank site.

4. Proposed drainfield/replacement site is 150' from

   septic holding tank. Drainfield site slopes gently

   to the NE at 16" over 100' (<1.5%). Site elevation averages

   1.5' lower than holding tank elevation at surface.

   Test pit was opened on drainfield site to ascertain stratigraphy.

   See summary of soils profile.

5. Proposed 20'X20" house site. Two stories plus basement;

   one bath. Small kitchen area. Open design – interior walls

   around bath only. ≈ 150' from high water mark of Yaak River

6. Proposed access road and parking area.

7. Existing floodplain.

8. Yaak River.

9. LOMA Case # 17-08-006.3A.

10. Existing NLI Easement.

11. Existing road.

12. Wetland area.

13. No build area with >30% slope to the river.

