LINCOLN COUNTY
DEPARTMENT OF ENVIRONMENTAL HEALTH
WASTEWATER TREATMENT AND DISPOSAL SYSTEM PERMIT

Issue Date: 02/13/2014 Expiration Date: 02/14/2015

Property Owner Kootenai Development Corp. c/o: Darryl Deibert

Address: [redacted]

Telephone: (Home) [redacted] (Work) [redacted]

Installer: Kootenai Sand & Gravel License No. 109

__XX__ New Installation _____ Existing System

_____ Repair _____ Replacement _____ Extension _____ Other

Describe: Multi-user wastewater collection and treatment system, per Engineered Plan by RLK Hydro, for Lots 1 through 9 of Barnaby Heights Subdivision in Eureka, Montana. ***Note: Each Lot must obtain an individual permit prior to installation of the home-site tank and effluent pump that will provide the lot's connection to this multi-user system.***

Parcel Description:

Legal: W-1/2 NW-1/4 S28 T35 R26

Address or Location: Lots 1 through 9 of Barnaby Heights Subdivsision

Approved Design Criteria For Barnaby Heights Subdivision Multi-user Wastewater Collection & Treatment System.

Septic Tank Size: 3000 gallons Dosing Tank Size: 3000 gallons Drainfield Size: 9560 Square Feet

SYSTEM MUST INCLUDE INSTALLATION OF EFFLUENT FILTER AT SEPTIC TANK OUTLET !!

Special Instructions: ***INSTALL MULTI-USER SYSTEM ACCORDING TO DEQ APPROVED ENGINEERED PLAN (E.Q. #10-1035), CIRCULAR DEQ 4, AND LINCOLN COUNTY WASTEWATER REGULATION. ANY DEVIATIONS FROM APPROVED PLAN MUST BE AUTHORIZED BY THE DEPARTMENT.*** **RLK HYDRO, INC. ENGINEER MUST ALSO SIGN-OFF ON THE CLOSURE STATEMENT.**

Issued By: *Kendra J. Lind, R.S.*

Closure Statement:

I, _____, have inspected this system and confirm that it is in compliance with the engineered plan, DEQ approval documents, the conditions of this permit, and the Lincoln County Wastewater Treatment and Disposal Regulation.

Signed: _____ *Date:*

Licensed Installer

Signed: _____ *Date:*

, PE #

NOTICE: The Department must be notified at least 48 hours prior to backfilling the system. Any system not inspected by the Department or its designated representative prior to closure is an illegal installation in violation of Lincoln County Health Board Regulation No. 3. Illegal installations may result in fines and/or requirements to remove or reconstruct the system.

406-293-7781

DISCLAIMER

This permit is not a guarantee by the Department that the system will function properly for a prescribed period of time.

RLK HYDRO INC.
Hydrology, Engineering and Environmental Consulting
484 N. Main St., P.O. Box 1579
Kalispell, Montana 59903
(406) 752-2025 FAX (406) 257-4125

Project Title: Barnaby Heights Subdivision

Drawing Title: Drainfield Plan View

Revisions

Notes

Project Manager: SR
Drawn By: SW
Reviewed By: SR
Date: 12/13/2013
File Name/View: 12014A Barnaby Heights - AsBuilt.vwx

Scale: Not to Scale
Project ID: 12.014A
Drawing No: 2