LINCOLN COUNTY
DEPARTMENT OF ENVIRONMENTAL HEALTH
WASTEWATER TREATMENT AND DISPOSAL SYSTEM PERMIT

Issue Date: 10/28/2013

Expiration Date: 10/29/2014

Property Owner: Lillia Enterprises LLC

c/o: Rick Vredenburg

Address: [redacted]

Telephone: (Home) [redacted] (Work) [redacted]

Installer: Gideon Yutzy

License No. 113

_x_ New Installation ____ Existing System

____ Repair ____ Replacement ____ Extension ____ Other

Describe: Sized for 2 - 2 bedroom homes (450 GPD), pressure dosed with chambers

Parcel Description:

Legal: S16T34NR25W Lot 2 Dickey Lake Lagoon Rewrite

Address or Location: 365 Hidden Cove Dr.

Approved Design Criteria:

Bedrooms 2 – 2BR

Septic Tank Size: 1500 gallons

Dosing Tank: 500 gallons

Drainfield Size: 376 Linear Feet

SYSTEM MUST INCLUDE INSTALLATION OF EFFLUENT FILTER AT SEPTIC TANK OUTLET !!

Special Instructions: INSTALL PRESSURE DOSED SYSTEM ACCORDING TO LAYOUT, DEQ-4 AND LINCOLN COUNTY WASTEWATER REGULATION #3. ANY DEVIATIONS FROM APPROVED PLAN MUST BE AUTHORIZED BY THE DEPARTMENT.

Issued By: Erik Leigh, RS

Closure Statement:

I, _____, *have inspected this system and found it to be in compliance with the conditions of the permit, and the Lincoln County Wastewater Treatment and Disposal Regulation.*

Signed: _____ *Date:* _____

Title: _____

NOTICE: The Department must be notified at least 48 hours prior to backfilling the system. Any system not inspected by the Department or its designated representative prior to closure is an illegal installation in violation of Lincoln County Health Board Regulation No. 3. Illegal installations may result in fines and/or requirements to remove or reconstruct the system.

406-283-2442

DISCLAIMER

This permit is not a guarantee by the Department that the system will function properly for a prescribed period of time.

LOT LAYOUT

LOT 2 Dickey Lake Lagoon rewrite
SE 1/4 sec. 16 T 34 N. R 25 W

