LINCOLN COUNTY
SEPTIC SYSTEM PERMIT NO. Replacement

ISSUED TO: PAUL STEBBINS DATE: 2-11-86

ADDRESS: [redacted] PHONE: [redacted]

ISSUED BY (sign.) John D. Peterson, RS.

INSPECTION BY (sign.) _____ DATE: _____

(You must notify the Department of Environmental Health a minimum of 8 working day hours before backfilling the septic system, so that it can be inspected.)

CONTRACTOR: M. Orr

DESCRIPTION OF SYSTEM:

LOCATION OF PROPOSED SYSTEM Northwood Manor - Riverview Add Lots 1-2

SEPTIC TANK 1000 gal. ABSORPTION AREA: 240 ft²

SEWAGE DISCHARGE — gal/day No. OF BEDROOMS 3

WATER SUPPLY SOURCE well SOIL Rocky Silt Loam SLOPE 0-½%

Drainfield INSTRUCTIONS: Dig a ditch 120' long x 2½-3' deep x 2' wide according to lot layout & septic system regs. Slope of pipe should not exceed a 1% drop.

Replace existing corroded metal tank w/ new 1,000 gal tank

SKETCH OF LOT LAYOUT:

