LINCOLN COUNTY
SEPTIC SYSTEM PERMIT NO. New

ISSUED TO: Mike Gannon DATE: 11-12-86

ADDRESS: [redacted] PHONE: [redacted]

ISSUED BY (sign.) John W Peterson, RS

INSPECTION BY (sign.) _____ DATE: _____

(You must notify the Department of Environmental Health a minimum of 8 working day hours before backfilling the septic system, so that it can be inspected.)

CONTRACTOR: Kootenusa P & E

DESCRIPTION OF SYSTEM:

LOCATION OF PROPOSED SYSTEM Gut Crk Rd 2½ mi. Sec 16 T35N R27W

SEPTIC TANK 1,000 gal. ABSORPTION AREA: 360 ft²

SEWAGE DISCHARGE ~ gal/day No. OF BEDROOMS 4

WATER SUPPLY SOURCE Spring SOIL gravelly loam SLOPE 2%

INSTRUCTIONS: Drain field Dig a ditch 180' long x 2½-3' deep x 2' wide according to lot layout & septic system reg's. Slope of pipe should not exceed a 10% drop.

SKETCH OF LOT LAYOUT:

