# LINCOLN COUNTY
# DEPARTMENT OF ENVIRONMENTAL HEALTH
# WASTEWATER TREATMENT AND DISPOSAL SYSTEM PERMIT

Issue Date: 11/17/2009 Expiration Date: 11/18/2010

Property Owner: Howard Mann c/o: Bill Merritt 9677 Hwy 2 N

Address: [redacted]

Telephone: (Home) [redacted] (Work)

Installer: Kootenai Valley Contractors License No. 76

__XX__ New Installation _____ Existing System

_____ Repair _____ Replacement _____ Extension _____ Other

Describe: Installing Pressure-dosed system.

*Parcel Description*:

Legal: Lot 28 in Block 3 of Wilderness Plateau

Address or Location: 101 Snowshoe Lane

*Approved Design Criteria*:

# Bedrooms: 2 Septic Tank Size: 1000 gallons Drainfield Size: 270 Square Feet

Dosing Tank Size: 500 gallons

**SYSTEM MUST INCLUDE INSTALLATION OF EFFLUENT FILTER AT SEPTIC TANK OUTLET !!**

***Special Instructions: INSTALL PRESSURE-DOSED SYSTEM ACCORDING TO LAYOUT, DEQ-4 AND LINCOLN COUNTY WASTEWATER REGULATION #3. ANY DEVIATIONS FROM APPROVED PLAN MUST BE AUTHORIZED BY THE DEPARTMENT.***

**Issued By:** *Kendra J. Lind, R.S.*

*Closure Statement:*

*I, _____, have inspected this system and found it to be in compliance with the conditions of the permit, and the Lincoln County Wastewater Treatment and Disposal Regulation.*

*Signed:* _____ *Date:* _____

*Title:* _____

**NOTICE: The Department must be notified at least 48 hours prior to backfilling the system. Any system not inspected by the Department or its designated representative prior to closure is an illegal installation in violation of Lincoln County Health Board Regulation No. 3. Illegal installations may result in fines and/or requirements to remove or reconstruct the system.**

**406-293-7781**

# LOT LAYOUT

